	TECHNICAL SPECIFICATION		Nr: I-ET-3010.2E-5121-600-P4X-002
	CLIENT: SRGE		SHEET: 1 of 15
	JOB: REFERENCE HULL 01		
	AREA: -		
SRGE	TITLE: POTABLE WATER MAKER SYSTEM (UM-5121501A/B) (Z-5121501A/B)		INTERNAL
			ESUP

File No.: MICROSOFT WORD 2016 – I-ET-3010.2E-5121-600-P4X-002_A.docx

INDEX OF REVISIONS

REV.	DESCRIPTION AND/OR REVISED SHEETS
0	ORIGINAL ISSUE
A	REVISED WHERE INDICATED

	REV. 0	REV. A	REV. B	REV. C	REV. D	REV. E	REV. F	REV. G	REV. H
DATE	SEP/05/22	DEC/07/22							
PROJECT	ENE	ENE							
EXECUTION	PMX4	PMX4							
CHECK	U4WK	BYA6							
APPROVAL	UPDM	CXZ0							

THE INFORMATION CONTAINED IN THIS DOCUMENT IS PETROBRAS PROPERTY AND MAY NOT BE USED FOR PURPOSES OTHER THAN SPECIFICALLY INDICATED HEREIN.

THIS FORM IS PART OF PETROBRAS N-381 REV.M ANNEX A – FIGURE A.1.



TITLE: **POTABLE WATER MAKER SYSTEM
(UM-5121501 A/B) (Z-5121501A/B)**

INTERNAL

ESUP

TABLE OF CONTENTS

PAGE

1. INTRODUCTION	4
1.1. OBJECTIVE.....	4
1.2. DEFINITIONS	4
1.3. ABBREVIATIONS	4
2. NORMATIVE REFERENCES	4
2.1. INTERNATIONAL CODES, RECOMMENDED PRACTICES AND STANDARDS	4
2.2. BRAZILIAN CODES AND STANDARDS.....	5
2.3. CLASS APPROVAL AND CERTIFICATION	5
3. REFERENCE DOCUMENTS	5
3.1. REFERENCE HULL 01	5
3.2. TYPICAL DOCUMENTS.....	5
3.3. SPECIFIC PROJECT DOCUMENTS	7
4. DESIGN REQUIREMENTS.....	8
4.1. DESIGN CONDITIONS	8
4.2. SAFETY REQUIREMENTS.....	8
4.3. NOISE AND VIBRATIONS	9
4.4. MOTIONS AND ACCELERATION	9
5. SCOPE OF SUPPLY.....	9
5.1. PACKAGE OF EQUIPMENT	9
5.2. EQUIPMENT LOCATION.....	10
6. PACKAGE SPECIFICATION.....	10
6.1. POTABLE WATER MAKER (UM-5121501A/B)	10
6.2. ULTRAVIOLET STERILIZATION UNIT (Z-5121501 A/B)	11
7. GENERAL REQUIREMENTS	11
7.1. ELECTRICAL REQUIREMENTS.....	11
7.2. INSTRUMENTATION AND AUTOMATION REQUIREMENTS.....	12
7.3. PAINTING REQUIREMENTS.....	12
7.4. SKIDS LAYOUT AND FOUNDATION REQUIREMENTS	12
7.5. AVAILABLE ON BOARD	13
7.6. NAMEPLATES AND TAG NUMBERING.....	13
8. PACKAGE MANUFACTURING AND DELIVERY REQUIREMENTS.....	13
8.1. GENERAL.....	13



TECHNICAL SPECIFICATION

Nr:

I-ET-3010.2E-5121-600-P4X-002

REV.

A

SHEET: 3 of 15


TITLE:

**POTABLE WATER MAKER SYSTEM
(UM-5121501 A/B) (Z-5121501A/B)**

INTERNAL

ESUP

8.2. WELDING	14
8.3. DOCUMENTATION	14
8.4. SPARE PARTS.....	14
8.5. INSPECTION AND TESTS.....	14
8.6. PRESERVATION, PACKING AND TRANSPORTATION.....	15
8.7. PRE-COMMISSIONING AND COMMISSIONING.....	15

	TECHNICAL SPECIFICATION	Nr: I-ET-3010.2E-5121-600-P4X-002	REV. A
	-		SHEET: 4 of 15
	TITLE: POTABLE WATER MAKER SYSTEM (UM-5121501 A/B) (Z-5121501A/B)		INTERNAL
		ESUP	

1. INTRODUCTION

1.1. OBJECTIVE

The purpose of this technical specification is to describe the minimum requirements for the design, manufacturing, assembly, supply, installation, commissioning and tests of Potable Water Maker (UM-5121501A/B) and Ultraviolet Sterilization Unit (Z-5121501A/B) in conformance with relevant regulations and **REFERENCE HULL 01** basic design documentation.

1.2. DEFINITIONS

PACKAGE: It is defined as an assembly of equipment supplied interconnected, tested and ready to operate, requiring only the available utilities from the Unit for the Package operation.

PACKAGER: It is defined as the responsible for project, assembly, construction, fabrication, testing and furnishing of the Package.

All definitions are found on I-ET-3010.00-1200-940-P4X-002 – GENERAL TECHNICAL TERMS

1.3. ABBREVIATIONS

CS	Classification Society
FAT	Factory Acceptance Tests
FPSO	Floating Production Storage and Offloading Unit
SOS	Supervisory and Operation System
SOS-HMI	Human Machine Interface of SOS

2. NORMATIVE REFERENCES

2.1. INTERNATIONAL CODES, RECOMMENDED PRACTICES AND STANDARDS

The equipment will be designed and manufactured in accordance with the following codes and standards, if not mentioned otherwise.

- ANSI American National Standards Institute
- ASME American Society of Mechanical Engineers
- DIN German National Standard Code
- EN European Standards
- ISO International Standard Organization
- IMO – International Maritime Organization – MPEC.227 (64)

- VDE / IEC German National Electric Standard Codes / International Electric Codes
- Classification Society defined for the Hull scope.

2.2. BRAZILIAN CODES AND STANDARDS

- NR – Brazilian Federal Government Regulatory Norms (Normas Regulamentadoras NRs)
- NORMAM-01 – Normas da Autoridade Marítima para Embarcações Empregadas na Navegação em Mar Aberto;
- Brazilian Government Ministry of Healthy Regulation "PORTARIA DE CONSOLIDAÇÃO Nº 5, DE 28 DE SETEMBRO DE 2017", Anexo XX. – “Consolidation Ordinance No. 5 of the Ministry of Health, 28th September 2017 on Annex XX”.
- ANVISA RDC 72/2009.

2.3. CLASS APPROVAL AND CERTIFICATION

The PACKAGE shall be designed, manufactured and tested according to the design reference documents, normative requirements and in accordance with the latest editions of Classification Society Rules, Regulations and Standards.

3. REFERENCE DOCUMENTS

3.1. REFERENCE HULL 01

REF DOC NUMBER	REF DOC NAME
HULL SYSTEMS	
I-DE-3010.2E-5115-944-P4X-002	FRESH, HOT AND POTABLE WATER SYSTEM
I-DE-3010.2E-5115-944-P4X-003	FRESH, HOT AND POTABLE WATER SYSTEM DISTRIBUTION
I-MD-3010.2E-1200-940-P4X-027	DESCRIPTIVE MEMORANDUM - HULL SYSTEMS
OUTFITTING	
I-DE-3010.2E-1351-140-P4X-001	HULL GENERAL NOTES AND TYPICAL DETAILS

3.2. TYPICAL DOCUMENTS

REF DOC NUMBER	REF DOC NAME
GENERAL	
I-ET-3000.00-0000-940-P4X-002	SYMBOLS FOR PRODUCTION UNITS DESIGN
I-ET-3010.00-1200-940-P4X-002	GENERAL TECHNICAL TERMS
I-ET-3000.00-1200-940-P4X-001	TAGGING PROCEDURE FOR PRODUCTION UNITS DESIGN
CONSTRUCTION	
I-ET-3010.00-1200-955-P4X-001	WELDING
I-ET-3010.00-1000-970-P4X-002	REQUIREMENTS FOR NDT
I-ET-3010.00-1200-955-P4X-002	REQUIREMENTS FOR WELDING INSPECTION
I-ET-3010.00-0000-970-P4X-001	REQUIREMENTS FOR PROCEDURES AND PERSONNEL QUALIFICATION AND CERTIFICATION
MECHANICAL	
I-ET-3010.00-1352-130-P4X-001	FLOOR GRATINGS, TRAY SYSTEMS AND GUARDRAILS MADE OF COMPOSITE MATERIALS.
I-ET-3010.00-1200-300-P4X-001	NOISE AND VIBRATION CONTROL REQUIREMENTS
PAINTING	
I-ET-3010.00-1200-956-P4X-002	GENERAL PAINTING
DR-ENGP-I-1.15	COLOR CODING
SAFETY	
I-ET-3010.00-5400-947-P4X-002	SAFETY SIGNALING
DR-ENGP-M-I-1.3	SAFETY ENGINEERING
PIPING	
I-ET-3010.00-1200-251-P4X-001	REQUIREMENTS FOR BOLTING MATERIALS

ELECTRICAL

I-DE-3010.00-5140-700-P4X-003	GROUNDING INSTALLATION TYPICAL DETAILS
I-ET-3010.00-5140-700-P4X-001	SPECIFICATION FOR ELECTRICAL DESIGN FOR OFFSHORE UNITS
I-ET-3010.00-5140-700-P4X-002	SPECIFICATION FOR ELECTRICAL MATERIAL AND EQUIPMENT FOR OFFSHORE UNITS
I-ET-3010.00-5140-700-P4X-003	ELECTRICAL REQUIREMENTS FOR PACKAGES FOR OFFSHORE UNITS
I-ET-3010.00-5140-712-P4X-001	LOW-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS

INSTRUMENTATION AND AUTOMATION

I-ET-3010.00-1200-800-P4X-002	AUTOMATION, CONTROL AND INSTRUMENTATION ON PACKAGE UNITS
I-ET-3010.00-1200-800-P4X-013	GENERAL CRITERIA FOR INSTRUMENTATION PROJECTS
I-ET-3010.00-5520-888-P4X-001	AUTOMATION PANELS
I-ET-3010.00-1200-800-P4X-015	REQUIREMENTS FOR TUBING AND FITTING (ALIGNED TO IOGP-JIP33 S-716)

3.3. SPECIFIC PROJECT DOCUMENTS

REF DOC NUMBER	REF DOC NAME
GENERAL	
I-DE-GENERAL ARRANGEMENT	GENERAL ARRANGEMENT
I-DE- AREA CLASSIFICATION – GENERAL	AREA CLASSIFICATION – GENERAL
I-ET-AUTOMATION INTERFACE OF PACKAGE UNITS	AUTOMATION INTERFACE OF PACKAGE UNITS
I-ET-METOCEAN DATA	METOCEAN DATA

I-RL-GENERAL SPECIFICATION FOR AVAILABLE UTILITIES	GENERAL SPECIFICATION FOR AVAILABLE UTILITIES
I-RL-MOTION ANALYSIS	MOTION ANALYSIS

Table 1 – Reference Documents

NOTE: Item 3.3 documents title and number may vary slightly from one project to another. Project’s document list shall be consulted in order to verify the correct document number and title design requirements

4. DESIGN REQUIREMENTS

4.1. DESIGN CONDITIONS

- 4.1.1. PACKAGE Equipment shall be designed for a 30-year life in a corrosive offshore environment without the need for replacement of any major component due to wear, corrosion, fatigue, or material failure.
- 4.1.2. PACKAGER shall design the equipment for the full range of operational conditions as specified in this technical specification.
- 4.1.3. PACKAGE Equipment shall be designed with the compliance of the normative and design requirements as stated in this specification and complying with the technical parameters stated on the above item 3 REFERENCE HULL 01 documents.
- 4.1.4. All elements of the PACKAGE shall be of proven design and well within the manufacturer’s actual experience.

4.2. SAFETY REQUIREMENTS

- 4.2.1. Personnel safety protection shall be provided according to Brazilian Regulatory Norms (NR) issued by Brazilian Government.
- 4.2.2. Warning signs in Brazilian Portuguese language shall be provided where risk of personnel injury exist.
- 4.2.3. Rotating equipment outer parts, such as pulleys, couplings, belts and flywheels, shall have rigid protection, manufactured with aluminum ASTM B211 and shall be capable of being easily removed.
- 4.2.4. In accordance with the requirements of SOLAS II-1, Regulation 3-5, and MSC.1/Circ. 1379, all equipment and material to be supplied by PACKAGER must be “asbestos free”.
- 4.2.5. Safety signaling shall be in full compliance with I-ET-3010.00-5400-947-P4X-002 – SAFETY SIGNALING.
- 4.2.6. Double block & bleed arrangements are required for isolation of equipment in piping classes of 300# and above.

4.3. NOISE AND VIBRATIONS

4.3.1. Noise and vibrations limits shall be in conformance with I-ET-3010.00-1200-300-P4X-001 – NOISE AND VIBRATION CONTROL REQUIREMENTS.

4.4. MOTIONS AND ACCELERATION

4.4.1. All equipment shall be able to withstand with the UNIT subjected to 100-year return period environmental conditions.

4.4.2. All equipment shall be able to operate with the UNIT subjected to 1-year return period environmental conditions.

4.4.3. All environmental conditions are defined in I-ET-METOCEAN DATA.

4.4.4. For the Hull loading conditions details and the maximum designed operational trim and heel inclinations refer to I-ET-3010.00-1350-960-P4X-003 – DESIGN REQUIREMENTS - NAVAL ARCHITECTURE.

4.4.5. For the design data and information regarding motion requirements refer to I-RL-MOTION ANALYSIS.

4.4.6. PACKAGE is also to withstand inertial forces during transportation from construction site to the final offshore location.


5. SCOPE OF SUPPLY

5.1. PACKAGE OF EQUIPMENT

5.1.1. PACKAGER shall supply the following items:

	TAG	Description	Qty
1	UM-5121501A/B	POTABLE WATER MAKER	2x100%
2	FT-UM-5121501A/B	POTABLE WATER MAKER FILTER	2X100%
3	Z-5121501A/B	ULTRAVIOLET STERILIZER UNIT	2X100%
4	PN-Z-5121501A/B	ULTRAVIOLET STERILIZER CONTROL PANEL	2X100%

Table 2 – Scope of Supply

	TECHNICAL SPECIFICATION	Nr: I-ET-3010.2E-5121-600-P4X-002	REV. A
	-		SHEET: 10 of 15
	TITLE: POTABLE WATER MAKER SYSTEM (UM-5121501 A/B) (Z-5121501A/B)		INTERNAL
ESUP			
<p>5.1.2. All Skid control valves shall also be included on the PACKAGER scope of supply.</p> <p>5.1.3. PACKAGE logic for control and automation shall be designed and supplied by PACKAGER.</p> <p>5.1.4. Additionally, PACKAGE scope of supply shall include any other item inside the limits of the skid as valves, instruments, interconnection piping, accessories, electrical and power devices and any other device to ensure the PACKAGE safe operation and under the design and operational limits defined by this Technical Specification.</p> <p>5.2. EQUIPMENT LOCATION</p> <p>5.2.1. POTABLE WATER MAKER SYSTEM shall be installed in Engine Room, which is a closed and non-classified compartment, as defined in I-DE-AREA CLASSIFICATION - GENERAL</p> <p>5.2.2. Potable Water Makers (UM-5121501A/B) and Ultraviolet Sterilizer Unit (Z-5121501A/B) shall be installed in separate skids.</p> <p>5.2.3. Potable Water Makers (UM-5121501A/B) shall be installed downstream the Fresh Water Hydrophore Unit (Z-5115501) and upstream the Ultraviolet Sterilizer Unit (Z-5121501A/B).</p> <p>5.2.4. For equipment location both I-DE-GENERAL ARRANGEMENT and I-DE-AREA CLASSIFICATION - GENERAL shall be considered.</p> <p>6. PACKAGE SPECIFICATION</p> <p>6.1. POTABLE WATER MAKER (UM-5121501A/B)</p> <p>6.1.1. Two identical Potable Water Maker (UM-5121501A/B) shall be supplied in a configuration 2 x 100% and each of the equipment shall have capacity for 15 m³/h of water maker.</p> <p>6.1.2. Each of the Potable Water Maker (UM-5121501A/B) shall be able to operate with any of the Ultraviolet Sterilizer Unit (Z-5121501A/B).</p> <p>6.1.3. Potable Water Maker Filter (FT-UM-5121501A/B) shall be designed according to the PACKAGER / MANUFACTURER standard.</p> <p>6.1.4. Potable water parameters shall reach the quality standard of the regulation stated by the Brazilian Government Ministry of Health: "PORTARIA DE CONSOLIDAÇÃO Nº 5, DE 28 DE SETEMBRO DE 2017, Anexo XX" - "Consolidation Ordinance No. 5 of the Ministry of Health, 28th September 2017 on Annex XX" and "RESOLUÇÃO Nº 72, DE 29 DE DEZEMBRO DE 2009" – ANVISA RDC 72/2009.</p> <p>6.1.5. Each Potable Water Maker (UM-5121501A/B) shall have a flange connection for equipment draining purpose.</p>			

6.2. ULTRAVIOLET STERILIZATION UNIT (Z-5121501 A/B)

- 6.2.1. Ultraviolet Sterilizer Unit (Z-5121501 A/B) shall follow the UV sterilizing principle.
- 6.2.2. Ultraviolet Sterilizer Unit (Z-5121501 A/B) shall be supplied in a configuration 2x100% and each of the equipment shall have capacity for 15 m³/h.
- 6.2.3. The UV Lamps shall be automatically turned-off, preventing failures caused by UV Lamps over-temperature, caused by low or no water flow through Ultraviolet Sterilizer Unit (Z-5121501 A/B)
- 6.2.4. Ultraviolet Sterilizer Unit (Z-5121501 A/B) shall be provided with an Ultraviolet Sterilizer Control Panel (PN-Z-5121501) in accordance with PACKAGER / MANUFACTURER's standard. At least the following functions shall be provided:
- i. Sterilizing process self control.
 - ii. UV lamps failure monitoring.
 - iii. UV lamps age monitoring.
- 6.2.5. Single block valves are used for the selection of each of equipment Potable Water Makers (UM-5121501A/B) and Ultraviolet Sterilizer Unit (Z-5121501A/B) are to be operational.
- 6.2.6. Potable water after Ultraviolet Sterilizer Unit (Z-5121501A/B) shall be destined to Accommodation Distribution, to eye washing stations and sinks and to Calorifier Units (Z-5125501).
- 6.2.7. Each Ultraviolet Sterilizer Unit (Z-5121501A/B) shall have a flange connection for equipment draining purpose.

7. GENERAL REQUIREMENTS

7.1. ELECTRICAL REQUIREMENTS

- 7.1.1. Electrical equipment and material shall comply with requirements of the following references:
- a) I-ET-3010.00-5140-700-P4X-002 – SPECIFICATION FOR ELECTRICAL MATERIAL AND EQUIPMENT FOR OFFSHORE UNITS.
 - b) I-ET-3010.00-5140-712-P4X-001 – LOW-VOLTAGE INDUCTION MOTORS FOR OFFSHORE UNITS.
 - c) I-ET-3010.00-5140-700-P4X-003 – ELECTRICAL REQUIREMENTS FOR PACKAGES FOR OFFSHORE UNITS.
 - d) I-ET-3010.00-5140-700-P4X-003 – ELECTRICAL REQUIREMENTS FOR PACKAGES FOR OFFSHORE UNITS.



TITLE:

**POTABLE WATER MAKER SYSTEM
(UM-5121501 A/B) (Z-5121501A/B)**

INTERNAL

ESUP

- e) I-ET-3010.00-5140-700-P4X-001 – SPECIFICATION FOR ELECTRICAL DESIGN FOR OFFSHORE UNITS and I-DE-3010.00-5140-700-P4X-003 – GROUNDING INSTALLATION TYPICAL DETAILS.

7.2. INSTRUMENTATION AND AUTOMATION REQUIREMENTS

7.2.1. PACKAGE instrumentation and control design shall fulfill the requirements of the following technical specifications:

- a) I-ET-3010.00-1200-800-P4X-002 – AUTOMATION, CONTROL AND INSTRUMENTATION ON PACKAGE UNITS.
- b) I-ET-3010.00-1200-800-P4X-013 – GENERAL CRITERIA FOR INSTRUMENTATION PROJECTS.
- c) I-ET-AUTOMATION INTERFACE OF PACKAGE UNITS.
- d) I-ET-3010.00-5520-888-P4X-001 – AUTOMATION PANELS.

7.3. PAINTING REQUIREMENTS

7.3.1. Painting and coating in accordance with I-ET-3010.00-1200-956-P4X-002 – GENERAL PAINTING and DR-ENGP-I-1.15 COLOR CODING.

7.3.2. All components shall be delivered fully painted/coated, unless otherwise indicated on this specification.

7.3.3. The performed pre-treatment and complete coating shall be in accordance with the paint manufacturer's data sheets.

7.4. SKIDS LAYOUT AND FOUNDATION REQUIREMENTS

7.4.1. PACKAGE components detailed on item 6 which are supplied assembled on skids shall follow the below minimum requirements.

7.4.2. PACKAGE skid structure shall be designed to withstand the design conditions mentioned on item 4.4 and to ensure the lifting conditions on manufacturing site and shipyard. Lifting lugs shall be provided according to PACKAGER lifting procedure.

7.4.3. The Skid main frame shall be all welded construction. Structural skid welds, including lifting facilities shall be continuous and shall comply with AWS D1.1 (structural welding code) and CS Rules.

7.4.4. Skid structure shall be designed to be welded to the supporting structure unless otherwise specified.

7.4.5. PACKAGE skid layout and arrangement shall be designed to provide sufficient access to pumps, instruments, equipment, and control panels so as to ease the operability and maintenance with safe conditions. Instruments and valves shall be installed on a suitable height to allow safe access for monitoring, operation, and

maintenance.

7.4.6. All necessary maintenance davits, monorails, padeyes or trolleys shall be provided to ensure the safe and easy maintenance conditions.

7.4.7. Access ladders, platforms, gratings and any other access device shall comply with I-ET-3010.00-1352-130-P4X-001 - FLOOR GRATINGS, TRAY SYSTEMS AND GUARDRAILS MADE OF COMPOSITE MATERIALS. Metallic material is also acceptable and I-DE-3010.2E-1351-140-P4X-001 – HULL GENERAL NOTES AND TYPICAL DETAILS, item 3.23, shall be followed for metallic grating requirements.

7.4.8. PACKAGE skid shall have a drip pan to collect drained water from the equipment with drain flanges for the connection with the Hull draining system.

7.4.9. PACKAGE Equipment and components shall be located entirely within the skids / equipment base perimeter, including all equipment, piping, valves, electrical, instrumentation and controls.

7.5. AVAILABLE ON BOARD

7.5.1. For utilities available onboard refer to I-RL-GENERAL SPECIFICATION FOR AVAILABLE UTILITIES.

7.6. NAMEPLATES AND TAG NUMBERING

7.6.1. PACKAGER / MANUFACTURER Equipment shall have nameplates in Brazilian Portuguese language, made of stainless steel AISI 316L, with 3 mm minimum thickness and fixed by stainless steel (AISI 316L) bolts or fasteners on visible and accessible location.

7.6.2. Tagging of all instruments, electrical, mechanical and piping items, including valves, shall be carried out as detailed on I-ET-3000.00-1200-940-P4X-001 – TAGGING PROCEDURE FOR PRODUCTION UNITS DESIGN.


8. PACKAGE MANUFACTURING AND DELIVERY REQUIREMENTS

8.1. GENERAL

8.1.1. All materials and equipment supplied by PACKAGER / MANUFACTURER shall be brand new (not overhauled), field proven, free from defects and accepted by Owner and the Classification Society.

8.1.2. Materials and equipment shall be manufactured according to internationally recognized standards for the offshore oil drilling and production industries and shall be in conformance with the REFERENCE HULL 01 Design and Agreement specifications and requirements.

8.1.3. Field proven definition: Systems and equipment shall demonstrate satisfactory operation at least in 3 floating offshore installation units, operating under process conditions (pressure, flow, capacity and similar fluids) for a minimum of 24,000

	TECHNICAL SPECIFICATION	Nr: I-ET-3010.2E-5121-600-P4X-002	REV. A
	-		SHEET: 14 of 15
	TITLE: POTABLE WATER MAKER SYSTEM (UM-5121501 A/B) (Z-5121501A/B)		INTERNAL
ESUP			

hours. For rotating equipment, they must demonstrate operation with fluid, flow and discharge pressure similar to the design. Unproven designs or prototypes (including components) without offshore service will not be accepted.

8.2. WELDING

8.2.1. PACKAGE equipment, structures and piping welding, welding inspection, non-destructive testing (NDT), bolted joints assembly and piping fabrication and commissioning activities shall be performed in compliance with the following technical specifications:

- a) I-ET-3010.00-1000-970-P4X-002 – Requirements for NDT.
- b) I-ET-3010.00-1000-955-P4X-002 – Requirements for Welding Inspection.
- c) I-ET-3010.00-1000-955-P4X-001 – Welding.
- d) I-ET-3010.00-1200-200-P4X-001 – Requirements for Bolted Joints Assembly and Management.
- e) I-ET-3010.00-1200-200-P4X-115 – Requirements for Piping Fabrication and Commissioning.

8.3. DOCUMENTATION


8.3.1. For the PACKAGE documentation and data-book requirements refer to EXHIBIT III – DIRECTIVES FOR ENGINEERING.

8.3.2. Additionally, for the PACKAGE documentation, data-book requirements refer to EXHIBIT V – DIRECTIVES FOR PROCUREMENT.

8.4. SPARE PARTS

8.4.1. For the PACKAGE, spare parts, special tools, CS required spare parts and spare parts list recommended for two (2) years of operation refer to EXHIBIT V – DIRECTIVES FOR PROCUREMENT.

8.5. INSPECTION AND TESTS

 PETROBRAS	TECHNICAL SPECIFICATION	Nr: I-ET-3010.2E-5121-600-P4X-002	REV. A
	-		SHEET: 15 of 15
	TITLE:	POTABLE WATER MAKER SYSTEM (UM-5121501 A/B) (Z-5121501A/B)	
<p>8.5.1. For PACKAGE inspection, tests, factory acceptance test (FAT) and inspection release certificate (IRC), refer to EXHIBIT V – DIRECTIVES FOR PROCUREMENT.</p> <p>8.5.2. For PACKAGE inspection and test plan (ITP) requirements refer to EXHIBIT VII – DIRECTIVES FOR QUALITY ASSURANCE SYSTEM.</p> <p>8.6. PRESERVATION, PACKING AND TRANSPORTATION</p> <p>8.6.1. For PACKAGE preservation, packing and transportation requirements refer to EXHIBIT V – DIRECTIVES FOR PROCUREMENT.</p> <p>8.7. PRE-COMMISSIONING AND COMMISSIONING</p> <p>8.7.1. For PACKAGE pre-commissioning and commissioning requirements and, commissioning spare parts refer to EXHIBIT VIII – DIRECTIVES FOR COMMISSIONING.</p> <p>8.7.2. The system in which PACKAGE is included has the commissioning and site tests requirements detailed on I-MD-COMMISSIONING DESCRIPTIVE MEMORANDUM.</p>			